Brikito

Brikito DPR Kit · Free

DAILY PROGRESS REPORT

The 10-point DPR checklist

Tick every point before the report leaves site. A DPR that passes all ten lets your project manager decide tomorrow's work without calling the site.

Project	Date	Checked by

- [ ] **1 Header is complete**
  Project, block/tower, date, report number, weather and working hours.
- [ ] **2 Quantities have a location and a cumulative**
  Activity, floor/grid, unit, today's quantity and total to date. "Blockwork done" is not progress.
- [ ] **3 Planned vs actual for key activities**
  Show where the week's plan is ahead or behind, not just what happened.
- [ ] **4 Manpower split by trade and contractor**
  Masons, bar benders, carpenters and helpers counted separately, present and absent.
- [ ] **5 Machinery hours and idle time**
  Hours worked, idle or breakdown time, and the reason. It explains low output and supports hire bills.
- [ ] **6 Materials logged with GRN or challan numbers**
  Received, issued and closing balance for cement, steel and ready-mix concrete.
- [ ] **7 Every hindrance written as an action**
  What is blocked, since when, and who must act. "Waiting for drawing" is a complaint, not an action.
- [ ] **8 Quality trail recorded**
  Inspections, pour cards, cube sample IDs, tests and any non-conformities.
- [ ] **9 Safety recorded**
  Toolbox talk, incidents, near misses and permits issued today.
- [ ] **10 Tomorrow's plan and dated photos**
  Activities, crews and the inputs needed by what time, plus date-stamped photos of the main work.

Send it the same evening. A DPR written at 9 pm from memory is a log. Capture quantities, headcounts and deliveries during the day, from the people who saw them.



Stop rebuilding the DPR every night.
Brikito builds it automatically from your team's site chat, photos and voice notes, in 7 Indian languages. A person approves before it goes out.

Book a free demo →